

CERN
24 Jan 2002

Vienna Cooling Box


M.Pernicka, T.Bauer, M.Friedl (HEPHY Vienna)

Purpose Module tests for CMS Tracker and other accelerated ageing tests


Features

- Holds up to 10 modules
- Temperature range $-30\dots+70^{\circ}\text{C}$ (cooling or heating operation)
- TRHX monitoring and control
- Water cooled Peltier elements
- Linear power supply
- Remote control and monitoring
- Nitrogen flushing to reduce humidity

Web <http://cern.ch/friedl> → Cooling Box



Photos



Full system:

Cooling Box (right)

TRHX (center)


Power Supply (left)

PC control (back)



Cooling Box internals


Two temperature
sensors can be
placed by the user
(attached to
inserts here)



Backplane for
VUTRI and auxiliary
modules

Extra connector
(bottom right)
is for internal
temperature and
humidity sensors

Performance - no load



Full power, no load

Room \rightarrow -30°C : ≈ 1.5 hrs

$-30^{\circ}\text{C} \rightarrow +70^{\circ}\text{C}$: ≈ 40 min


Water flow ≈ 5 l/min

Legend:

Plates: cold side of Peltier elements

Modules: Inserted module transportation plates

Cooling – no load




Full power, no load

First-order system

Time constant: 44.5min

$T_\infty = -33^\circ\text{C}$ (depending on water temperature)

Heating – no load



Full power, no load


First-order system


Time constant: 42.2min

$T_\infty = 124^\circ\text{C}$ (depending on water temperature)
– extrapolation

We do not recommend operation above +70°C

Performance – 50W load




 Full power, 50W load

10 modules with 6 APVs
each dissipate $\approx 25\text{W}$ at
nominal settings

 Room $\rightarrow -20^\circ\text{C}$: $\approx 1.5\text{hrs}$

$-20^\circ\text{C} \rightarrow +70^\circ\text{C}$: $\approx 40\text{min}$

Cooling – no load




Full power, 50W load

First-order system

Time constant: 45.4min

$T_{\infty} = -23^{\circ}\text{C}$ (depending on water temperature)

Heating – no load



Full power, 50W load


First-order system

Time constant: 42.6min

$T_{\infty}=123^{\circ}\text{C}$ (depending on water temperature)
– extrapolation

We do not recommend operation above +70°C

Module transportation plate




Provided by Paolo Tempesta
(Paolo.Tempesta@ba.infn.it)

Tested with connectors: fits perfectly

Cooling test

Two temperature probes attached to transportation plate and to APV25 location

Module transportation plate



Full power, quick test
(cooling stopped before
reaching saturation)

Both transportation plate
and APV25 hybrid closely
follow plate temperature

Transportation plate
responds a bit faster than
plates because plate
sensors are located on
the outside edge (i.e.
thermal delay line)

Technical data

Peltier	2 elements with 350W max. each
Power supply	Dual channel linear power supply Each channel individually adjustable between 0...25V
TRHX	Temperature and humidity monitoring Remote control and monitoring of power supply
Temp. range	-25°C...+70°C (with 10 modules installed \approx 25W)
Time constant	\approx 44min (first order system)
Cooling speed	Room temperature \rightarrow -25°C: \approx 1.5hrs
Heating speed	-20°C \rightarrow +70°C: \approx 40min

Price list

Components	Cooling Box mechanics (including 2 Peltier elements, gas flow meter and bubbler)	CHF 3000
	Cooling Box power supply (dual linear 0...25V 15A)	CHF 1800
	TRHX_base + 3 combined sensors + 3 dual temperature sensors	CHF 1440
	Shipping	CHF 100
Payment	TID is preferred method	
Contact	Manfred Pernicka < pernicka@hephy.oeaw.ac.at > (Cooling box)	
	Markus Friedl < markus.friedl@cern.ch > (Power supply, TRHX)	